BRUHAT BANGALORE MAHANAGARA PALIKE

APPROVED SCHEDULE - B

BBMP/2012-13/RD/WORK_INDENT4580/CALL-4

Name of Work: Improvements to Roads, Drains and Asphlting to Roads in Venkategowda layout Kempapura 2nd Main in ward no. 7, Byatarayanapura.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of RAMSINGH CHANDRA NAIK	
				In Figures	In Words
1	1696.2	Removing BS Slab of drain and stacking.	Sqm	46.67	Rupees Forty Six and Sixty Seven Paise Only
2	1356.96	Refixing stone slabs of drains and pointing in CM 1:3.	Sqm	66.12	Rupees Sixty Six and Twelve Paise Only
3	339.24	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. (7.50cms thick)	Sqm	330.97	Rupees Three Hundred Thirty and Ninety Seven Paise Only
4	575.7	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications. MORTH Chapter 3.	Cum	61.21	Rupees Sixty One and Twenty One Paise Only
5	3838	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (167, I.No. 19.64) SR 2012-13	Cum	3.97	Rupees Three and Ninety Seven Paise Only
6	575.7	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 167, Item No. 20.18) SR 12-13	Cum	1111.92	Rupees One Thousand One Hundred Eleven and Ninety Two Paise Only
7	3838	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 172, Item No. 21.6) SR 12-13	Sqm	41.60	Rupees Forty One and Sixty Paise Only
8	95.95	KSRRB M500-18. Providing and laying semi dense bituminous concrete 25 mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No. 500.8 complete in all respects as per specifications. with 80/100 grade bitumen using 40-60 HMP using mechanical paver (P. 174, Item No. 21.20.5) SR	Cum	9437.19	Rupees Nine Thousand Four Hundred Thirty Seven and Nineteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92